


1. Do not scale this drawing - if in doubt ask.
 2. All sites to be checked on site prior to construction.
 3. This drawing is the copyright of the author.

IN STREET



North

Oil Tank

Remove chimney stack and slate over.

Existing concrete tile roof checked / replaced
 Now flush to roof vent inlet / outlets built into roof Ubink UB 11 or equal or with Code 4 lead flashings
 Existing Velux removed and roof made good.

New slate

New slate

New slate

New slate

Existing slate

Existing slate

Existing slate

Existing Velux

Existing Velux

Existing Velux

Roof Fan AIR OUT Restaurant

Chimney stack and flue reinstated.

Concrete slab

Wall

Rev A - BC Updates 31.07.2020
smith design associates
 Dumfries Leatherhead Glasgow
 30 Castle Street, Dumfries DG1 1DU
 dumfries@smithdesign.co.uk 01387 250579
 www.smithdesign.co.uk client

New Luce Community Trust

project Kenmuir Arms Proposed Refurbishment
 drawing Proposed Roof Plan original size A1
 scale 1:50 drawn JB
 date 16.03.2020 checked -
 status WARRANT passed -

job no. D2786 drawing no. AL(0)027 revision A